

Chapter 8: Procurement Plan

This section outlines the procurement strategy for materials required for the successful execution of the proposed two-storey Camp Kanc Villa and associated works. The procurement sequence follows the construction methodology, prioritizing materials before the activities where they are required. Material applications and quantities referenced in the construction methodology are used as the basis for planning. Supplier categories and lead times below are indicative procurement allowances and should be confirmed through supplier quotations and actual site schedules.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
Approved Selected Fill	Jed Tyrone	2–4 Days	Before backfilling and compaction	Keep covered and separated from organic soil; protect from excessive water.
Well-Graded ¾-in Gravel	Jed Tyrone	2–4 Days	Before foundation bedding/base works	Store on firm, drained ground; segregate from soil and debris.
Structural Reinforced Concrete, 28 MPa	Jed Tyrone	3–7 Days / scheduled batch	Before footing, column, beam, slab and structural pours	Protect cementitious components from contamination; place concrete according to scheduled pour.
Deformed Grade 40/60 Reinforcing Bars	Jed Tyrone	3–5 Days	Before reinforcement fabrication and structural framing	Store off ground on dunnage; cover from rain and salt exposure.
WWF (Welded Wire Fabric)	SMARTSAVER TRADING CORP.	3–7 Days	Before slab and applicable reinforcement works	Store flat, off ground, dry and protected from corrosion.
#16 GI Tie Wire	SMARTSAVER TRADING CORP.	1–3 Days	Before rebar fabrication and installation	Keep dry and covered; store coils off wet ground.
Phenolic/Marine Plywood Formwork	SMARTSAVER TRADING CORP.	3–5 Days	Before formwork erection	Store flat, elevated, dry and covered; avoid warping.
Timber for Formwork/Shoring	SMARTSAVER TRADING CORP.	2–5 Days	Before formwork, shoring and falsework	Stack on level dunnage under cover; keep dry and ventilated.
Concrete Hollow Blocks (6-in Exterior / 4-in Interior)	Jed Tyrone	3–7 Days	Before masonry works	Stack on level, dry surface; protect from damage and excessive moisture.
Cement-Sand Mortar	Jed Tyrone	1–3 Days	Before CHB laying and masonry works	Store cement dry and elevated; keep sand clean and separated.
Cement-Sand Screed	Jed Tyrone	1–3 Days	Before floor topping/screed works	Keep cement dry; store sand clean and covered.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
RC/Precast Sill	SMARTSAVER TRADING CORP.	5–10 Days	Before door/window installation and masonry finishing	Store level on dunnage; protect edges from impact.
PPR/HDPE Pipes	SMARTSAVER TRADING CORP.	3–7 Days	During plumbing rough-ins, before walls/slabs are closed	Store on supports, shaded and protected from impact/UV.
uPVC Sanitary/Waste/Vent Pipes	SMARTSAVER TRADING CORP.	3–7 Days	During sanitary rough-ins before plastering	Store straight, shaded, supported and capped.
Plumbing Valves and Fittings	SMARTSAVER TRADING CORP.	2–5 Days	Alongside pipe rough-ins and fixture installation	Keep boxed, dry, clean and protected from damage.
Plumbing Supports	SMARTSAVER TRADING CORP.	2–5 Days	During pipe installation	Store dry and organized by size; protect galvanized/coated surfaces.
Water Closet	SMARTSAVER TRADING CORP.	5–10 Days	After finished walls/floors and before final plumbing commissioning	Store boxed in dry, secure area; protect ceramic surfaces.
Lavatory	SMARTSAVER TRADING CORP.	5–10 Days	After wall/floor finishes and before final plumbing commissioning	Keep boxed and protected from impact.
Faucets	SMARTSAVER TRADING CORP.	3–7 Days	During fixture fit-out	Store boxed, dry and protected from scratches.
Mixer/Thermostatic Shower Set	SMARTSAVER TRADING CORP.	5–10 Days	During bathroom fit-out after rough-ins	Keep boxed and dry; protect finished surfaces.
Stainless/Porcelain Sink	SMARTSAVER TRADING CORP.	5–10 Days	During kitchen/bathroom fit-out	Store boxed on padded supports; avoid impact and staining.
Heavy-Duty Outdoor Hose Bibb	SMARTSAVER TRADING CORP.	3–7 Days	During exterior plumbing fit-out	Keep boxed and dry; protect threads.
Electric Water Heater	SMARTSAVER TRADING CORP.	7–14 Days	After electrical/plumbing rough-ins and before commissioning	Store upright, dry and protected from impact; follow manufacturer storage requirements.
Resort-Grade Bathtub	SMARTSAVER TRADING CORP.	7–14 Days	After bathroom finishes and before final fixture fit-out	Store in original packaging on level supports; protect finish.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
Automatic Booster Pump/Tank	SMARTSAVER TRADING CORP.	7–14 Days	After water supply rough-ins and before system commissioning	Store dry, covered and secure; protect motor/control components.
PVC/RSC Electrical Conduits	SMARTSAVER TRADING CORP.	3–7 Days	During electrical rough-ins before wall/slab closure	Store straight, shaded and protected from crushing.
Utility Boxes	SMARTSAVER TRADING CORP.	2–5 Days	With conduit and wiring rough-ins	Store dry, organized by type/size and protected from corrosion.
Junction Boxes	SMARTSAVER TRADING CORP.	2–5 Days	With electrical rough-ins	Store dry and protected from damage/corrosion.
Panel Boards	SMARTSAVER TRADING CORP.	7–14 Days	After major electrical rough-ins and before final electrical fit-out	Store indoors, dry, upright and locked against damage.
Electrical Outlets and Switches	SMARTSAVER TRADING CORP.	5–10 Days	During final electrical fit-out	Keep boxed, dry and clean; protect faceplates from scratches.
Lighting Fixtures	SMARTSAVER TRADING CORP.	7–14 Days	After ceiling/finish works are sufficiently complete	Store boxed indoors in a dry, secure area.
Galvanized/Painted Steel	SMARTSAVER TRADING CORP.	5–10 Days	Before metal works and fabrication	Store on dunnage under cover; keep dry and protected from salt contamination.
Marine-Grade SS316	SMARTSAVER TRADING CORP.	7–14 Days	Before railing/perimeter metalwork fabrication	Store covered, dry and segregated from carbon steel to prevent contamination.
Structural Steel C-Purlins/Tubular Framing	SMARTSAVER TRADING CORP.	7–14 Days	Before roof framing installation	Store off ground on dunnage; keep dry and secured against wind.
Steel Plates, Brackets and Anchors	SMARTSAVER TRADING CORP.	5–10 Days	Before roof/metal framing and anchoring works	Store dry, elevated and organized by fabrication package.
Fasteners	SMARTSAVER TRADING CORP.	2–5 Days	Before structural, roofing and metal installation	Store sealed, dry and organized by size/type.
Cementitious/Bituminous Damp-Proofing	SMARTSAVER TRADING CORP.	5–10 Days	Before damp-proofing and foundation protection works	Store sealed in dry, shaded area; protect from freezing/heat as applicable.
Pre-Painted GA26 Galvanized Steel Roofing	SMARTSAVER TRADING CORP.	7–14 Days	After roof framing is ready	Store on level supports under cover; prevent scratching and water entrapment.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
Pre-Painted GA24 Galvanized Steel Flashing	SMARTSAVER TRADING CORP.	7-14 Days	With roofing installation	Store flat or properly supported, dry and protected from scratches.
Pre-Painted GA24 Galvanized Steel Gutters	SMARTSAVER TRADING CORP.	7-14 Days	With roofing and roof drainage installation	Store supported and covered; prevent deformation.
Pre-Painted Galvanized Steel Ridge Roll	SMARTSAVER TRADING CORP.	5-10 Days	With roofing installation	Store dry, supported and protected from bending/scratching.
Moisture-Resistant Gypsum/Fiber-Cement Board	SMARTSAVER TRADING CORP.	5-10 Days	After wet works are substantially complete and before ceiling/wall finishing	Store flat, dry, elevated and covered; protect edges.
Fiber-Cement Soffit	SMARTSAVER TRADING CORP.	5-10 Days	After roof/exterior framing is ready	Store flat, dry and supported; protect edges.
PVC Vent/Louver	SMARTSAVER TRADING CORP.	5-10 Days	During exterior/interior finish installation	Store boxed, dry and protected from impact.
Cementitious/Elastic Waterproofing	SMARTSAVER TRADING CORP.	3-7 Days	Before wet-area and exterior waterproofing	Store sealed, shaded and dry; observe manufacturer shelf-life.
Waterproof Membrane/Cementitious System	SMARTSAVER TRADING CORP.	5-10 Days	Before wet-area, balcony/terrace and damp-proofing works	Store sealed, dry and within recommended temperature range.
Primer	SMARTSAVER TRADING CORP.	3-7 Days	Before painting and coating works	Store sealed in a cool, dry, ventilated area away from ignition sources.
Exterior/Interior Acrylic Coating	SMARTSAVER TRADING CORP.	3-7 Days	After surface preparation and primer/sealer application	Store sealed, shaded and temperature-controlled as required.
Interior Acrylic Latex	SMARTSAVER TRADING CORP.	3-7 Days	During interior painting after plastering and priming	Store sealed, dry and protected from extreme heat.
Sealer	SMARTSAVER TRADING CORP.	3-7 Days	Before final paint coats	Store sealed and shaded; observe shelf-life.
Marine-Grade Varnish	SMARTSAVER TRADING CORP.	3-7 Days	After wood surface preparation	Store sealed, cool and ventilated; keep away from ignition sources.
Anti-Corrosion Primer	SMARTSAVER TRADING CORP.	3-7 Days	Before metal painting/coating	Store sealed in a cool, dry, ventilated area; protect from ignition sources.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
Epoxy/Enamel Paint	SMARTSAVER TRADING CORP.	3–7 Days	After anti-corrosion primer and surface preparation	Store sealed, dry and ventilated; protect from heat and ignition.
Porcelain/Ceramic Floor Tiles	SMARTSAVER TRADING CORP.	5–10 Days	After screed has cured and before floor finishing	Store flat on firm supports; protect edges and faces from impact.
Polymer-Modified Tile Adhesive	SMARTSAVER TRADING CORP.	3–7 Days	Immediately before tile installation	Store dry and elevated; protect bagged product from moisture.
Polymer-Modified Grout	SMARTSAVER TRADING CORP.	3–7 Days	During tile installation and after adhesive curing	Store dry and sealed; protect from moisture.
Granite/Quartz	SMARTSAVER TRADING CORP.	7–14 Days	After final measurements and before countertop installation	Store upright on padded supports; protect edges and surfaces.
Porcelain/Glazed Ceramic Wall Tiles	SMARTSAVER TRADING CORP.	5–10 Days	After plastering/waterproofing and before wall tiling	Store flat, dry and protected from impact.
Natural/Engineered Stone	SMARTSAVER TRADING CORP.	7–14 Days	After substrate preparation and final measurements	Store on padded A-frames/supports; protect edges.
Solid-Core Engineered Wood Doors	SMARTSAVER TRADING CORP.	10–21 Days	After masonry openings are verified and finishes are ready	Store indoors, dry, flat and protected from moisture.
Solid-Core Laminated Interior/Bedroom Doors	SMARTSAVER TRADING CORP.	10–21 Days	During final carpentry/door fit-out	Store flat in dry indoor area; protect laminates from scratches.
PVC/Aluminum Doors	SMARTSAVER TRADING CORP.	7–14 Days	After final opening measurements and before fit-out	Store upright or as manufacturer recommends; protect frames and finishes.
Aluminum Bi-Folding Doors	SMARTSAVER TRADING CORP.	14–21 Days	After final opening dimensions are confirmed	Store upright, protected from impact, moisture and scratches.
Powder-Coated Aluminum Sliding Doors	SMARTSAVER TRADING CORP.	14–21 Days	After final opening measurements and before finish fit-out	Store upright on padded supports; protect powder coating and tracks.
6mm Tempered Glass	SMARTSAVER TRADING CORP.	7–14 Days	After frames/openings are ready for glazing	Store upright on approved padded racks in a dry, secure area.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
Laminated/Engineered Wood Pocket Doors	SMARTSAVER TRADING CORP.	10–21 Days	After pocket frames and wall dimensions are verified	Store flat, dry and protected from warping.
SS304/SS316 Door Hinges	SMARTSAVER TRADING CORP.	3–7 Days	Before door hanging	Store boxed, dry and segregated by type.
Stainless Door Levers/Knobs	SMARTSAVER TRADING CORP.	3–7 Days	During final door hardware installation	Store boxed and protected from scratches.
Heavy-Duty Entrance Locks	SMARTSAVER TRADING CORP.	5–10 Days	Before final entrance door installation	Store boxed in secure, dry area.
Heavy-Duty Deadbolts	SMARTSAVER TRADING CORP.	3–7 Days	During final door hardware installation	Store boxed, dry and secure.
Stainless/Rubber Door Stoppers	SMARTSAVER TRADING CORP.	2–5 Days	During final door hardware installation	Store boxed and dry.
Hardwood/PVC Baseboards	SMARTSAVER TRADING CORP.	5–10 Days	After wall and floor finishes are ready	Store flat, dry and protected from warping.
Wood/PVC Cornice	SMARTSAVER TRADING CORP.	5–10 Days	During ceiling/interior finishing	Store straight, dry and protected from impact.
Hardwood Stair Treads	SMARTSAVER TRADING CORP.	7–14 Days	After stair structure is cured and dimensions are verified	Store flat indoors, dry and protected from moisture.
Hardwood Newel	SMARTSAVER TRADING CORP.	7–14 Days	During stair and railing fit-out	Store indoors, dry and protected from impact.
Marine Plywood/Laminated Cabinet Materials	SMARTSAVER TRADING CORP.	5–10 Days	After final cabinet dimensions are confirmed	Store flat, elevated and dry; protect laminates and edges.
Powder-Coated Aluminum Sliding Windows	SMARTSAVER TRADING CORP.	10–21 Days	After final opening measurements and before glazing/finish completion	Store upright on padded supports; protect coating and glass.
Aluminum Awning Windows	SMARTSAVER TRADING CORP.	10–21 Days	After final opening measurements	Store upright, dry and protected from impact.
Fixed Aluminum/Glass Windows	SMARTSAVER TRADING CORP.	10–21 Days	After final opening measurements	Store upright on padded racks; protect glass and frames.
Frosted Toilet Awning Windows	SMARTSAVER TRADING CORP.	10–21 Days	After toilet openings and wall finishes are verified	Store upright, dry and protected from scratches.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
Powder-Coated Aluminum Double Casement Windows	SMARTSAVER TRADING CORP.	10–21 Days	After final opening measurements	Store upright on padded supports; protect powder coating.
Pool Waterproofing System	SMARTSAVER TRADING CORP.	5–10 Days	After pool structural concrete has cured and surfaces are prepared	Store sealed, shaded and dry; protect components from contamination.
Porcelain/Glass Mosaic Pool Tiles	SMARTSAVER TRADING CORP.	7–14 Days	After waterproofing passes testing	Store boxed, dry and protected from impact.
Stone/Porcelain Pool Coping	SMARTSAVER TRADING CORP.	7–14 Days	After pool structure and waterproofing are ready	Store on level padded supports; protect edges and surfaces.
Non-Slip Outdoor Pavers/Tiles	SMARTSAVER TRADING CORP.	5–10 Days	After pool deck/substrate preparation	Store on firm, level ground; protect from breakage and contamination.
Pool Piping, Valves and Fittings	SMARTSAVER TRADING CORP.	5–10 Days	During pool hydraulic rough-ins before concrete enclosure	Store capped, shaded and organized; protect fittings from dirt.
Pool Drains	SMARTSAVER TRADING CORP.	5–10 Days	Before pool structural concreting/rough-in closure	Store boxed and protected from damage and debris.
Pool Skimmer Assemblies	SMARTSAVER TRADING CORP.	5–10 Days	Before pool wall concrete casting	Store boxed, dry and protected from impact.
Pool Return Fittings	SMARTSAVER TRADING CORP.	5–10 Days	Before pool wall/floor concrete casting	Store boxed and protected from contamination.
Pool Main Drain Assemblies	SMARTSAVER TRADING CORP.	5–10 Days	Before pool structural concreting	Store boxed, dry and protected from damage.
Pool Circulation Pump	SMARTSAVER TRADING CORP.	7–14 Days	After piping/electrical connections are ready and before commissioning	Store dry, covered and secure; keep motor/control components protected.
Pool Filter Tank	SMARTSAVER TRADING CORP.	7–14 Days	With pool pump and filtration installation	Store upright on firm base, covered and protected from impact.
Pool Controls	SMARTSAVER TRADING CORP.	7–14 Days	During pool equipment installation and commissioning	Store indoors, dry and protected from moisture.

Major Material	Possible Suppliers	Lead Time	Delivery Schedule	Storage Requirements
Automatic Chlorinator/Salt or Chemical Dosing System	SMARTSAVER TRADING CORP.	7-14 Days	After circulation/filtration system installation and before commissioning	Store dry, secure and protected from chemicals/impact.
LED Underwater Pool Lights	SMARTSAVER TRADING CORP.	7-14 Days	After pool finishes and niches are ready; before final commissioning	Store boxed, dry and protected from impact; keep lenses/surfaces clean.
Pool Ladder	SMARTSAVER TRADING CORP.	7-14 Days	After pool coping/deck finishes and before final commissioning	Store covered, dry and protected from scratching.